

STABILIZATION TECHNOLOGY

VISHWA SAMUDRA ENGINEERING PVT LTD

AN ISO 9001:2015,14001:2015,ISO 45001:2018 CERTIFIED COMPANY



VISHWA SAMUDRA ENGINEERING PRIVATE LIMITED COMPANY PROFILE :

Incorporated on 26th August, 2016 as Bay Area Marine & Port Engineering Services Private Limited and renamed as M/s Vishwa Samudra Engineering Private Limited (VSE) on 5th October, 2017 with a vision -

"To be India's leading infrastructure creator pushing the boundaries of innovation and pursuing opportunities to build a sustainable future for everyone".

- The driving force behind VSEPL's ascending trajectory, **Mr. Chinta Sasidhar, Hon'ble Chairman** guides VSEPL by five prime principles as sustainability, integrity, innovation, ownership, transparency.
- ➤ VSEPL offers multi-disciplinary infrastructure services like Roads, Airports, Marine structures, Irrigation works, buildings etc., that address complex challenges and deliver turn-key projects by using advanced technologies.



SOIL STABILIZATION TECHNOLOGY - A GREEN INITIATIVE INTRODUCTION:

Soil Stabilization

A process in which binders/additives are added to existing soil to improve it's engineering properties

Full Depth Recycling

A pavement rehabilitation technique in which the full flexible pavement section and a pre-determined portion of the underlying materials are uniformly pulverised or blended resulting in a stabilised base course



In both process, **StabilRoad Additive** is being used in combination with cement to improve over conventional cement treated base (CTB)



SOIL STABILIZATION TECHNOLOGY - A GREEN INITIATIVE ADVANTAGES:

- Reduction in usage of aggregates, thereby reducing carbon footprints 85% saving in aggregates
- Usage of modern equipment for faster completion of projects Entire construction process is mechanized
- Reduction in construction time 7 days to complete 1 Lane km with asphalt
- Higher unconfined strength and higher modulus Average of 6 MPa and average modulus of 7500 MPa
- Increase in durability, resulting in very minimal life cycle cost Almost NIL cost over the last 5 years
- Lower cost of construction 5-10% depending on soils, traffic etc
- Can work in varied climatic zones in India Andaman, Leh Ladakh, Northeast states
- Can execute roads with varied design traffic conditions —Already executed <2 msa and >200 msa traffic



ECOLOGICAL BENEFITS OF STABILIZATION

Out of the executed **400+ lane km**, the following are:

- Fresh Soil/Aggregate SAVINGS 5,93,000 CUM
- Savings in terms of truck loads 36,000 TRUCKS
- Savings in fuel consumption 3,50,000 LITRES
- Carbon emission savings 7500 tons of CO2e

With these approaches of stabilization technology, we can achieve the target of NET-ZERO carbon emissions by 2070 as per Hon'ble Prime Minister's vision.





STEP1

SOIL/EXISTING ROAD PROFILING

STEP2

CEMENT SPREADING

STEP3

 STABILROAD SPREADING

STEP4

• RECYCLING

STEP5

COMPACTION



STEP 1: SOIL/EXISTING ROAD PROFILING



STEP 3: STABILROAD SPREADING



STEP 5: COMPACTION



STEP 2: CEMENT SPREADING



STEP 4: RECYCLING

CONTD.,




GRADING STEP6 **ROLLING** STEP7 **CURING** STEP8 SAMI LAYER/ GEO SYNTHETIC FABRIC STEP9 PRIME COAT STEP10 **BC LAYER** STEP11



STEP 7: ROLLING



STEP 9: SAMI LAYER



STEP 11: BC LAYER



STEP 6: GRADING



STEP 8: CURING



STEP 10: PRIME COAT





SOIL STABILIZATION TECHNOLOGY - A GREEN INITIATIVE CRRI FINAL REPORT

HIGHLIGHTS:

- The UCS value (11 MPa) of stabilized cores/samples is well within and above the IRC specified range (4.5 to 7 MPa in 7days) for cementitious bases
- All field stabilized cores/samples satisfied the durability test and residual strength is much higher than required as per IS SP
 89 2018
- The back calculated elastic moduli (6806 MPa) from FWD data are significantly higher than that of cement treated base (CTB) design value (5000 MPa)
- Elastic moduli for the StabilRoad stabilized bases are significantly higher (>5000 MPa) than that of conventional which enables to eliminate DBM layer in StabilRoad stabilized roads.
- The riding quality of all StabilRoad stabilized roads are good even after 3.5 years.
 CRRI Final Report



SOME OF THE PROJECTS EXECUTED BY VSE:

INFRASTRUCTURE:

- 1. KRISHNAPATNAM PORT, NELLORE
- 2. KATUPALLI PORT, CHENNAI

AIRPORTS:

1. GMR INTERNATIONAL AIRPORT, HYDERABAD

CITY ROADS:

- 1. NTR MARG, HYDERABAD
- 2. ECIL AS RAO NAGAR ROAD, HYDERABAD

NATIONAL HIGHWAYS:

- 1. NH4 ANDAMAN AND NICOBAR ISLANDS
- 2. NH104/77 BIHAR

STATE HIGHWAYS:

- 1. PURVANCHAL EXPRESSWAY SERVICE ROADS, UP
- 2. ANAYADI KOODAL ROAD, KERALA
- 3. LALRU MALAN ROAD, PUNJAB

RURAL ROADS:

- 1. SALIPETA PORANKI ROAD, VIJAYAWADA, ANDHRA PRADESH
- 2. AIIB WORKS, ANDHRA PRADESH Total: 859 KM
- 3. UPFDR WORKS 9 PACKAGES Total: 257 KM




CRUST CHANGE DUE TO STABILIZATION

■ TOTAL LENGTH: 2.265Km

AVERAGE UCS: 10.05 MPa

RESOURCE SAVINGS : 250 Trucks

SAVINGS IN % : 91%









SPREADING OF CEMENT

SPREADING OF STABILROAD ADDITIVE







RECYCLING

COMPACTION







GRADING



COMPACTION



COMPACTION

CURING





FINISHED ROAD




CRUST CHANGE DUE TO STABILIZATION

TOTAL LENGTH: 859 Km

AVERAGE UCS: 5.66 MPa

RESOURCE SAVINGS :29,800 Trucks

SAVINGS IN%: 92%







SPREADING OF CEMENT

SPREADING OF STABILROAD ADDITIVE






FULL DEPTH RECYCLING (FDR)







COMPACTION

CURING AFTER FINAL COMPACTION







FINISHED ROAD







PERFORMING LWD TEST ON STABILIZED BASE TO ASSESS THE STRENGTH OF STABILIZED BASE









STABILIZED BASE CORE SAMPLE - 28 DAYS



SEGMENT WISE AVERAGE UCS STRENGTH RESULTS

SEGMENT	UCS STRENGTH (MPa)		MODULI VALUES (MPa)		AVG TOTAL SAVINGS NATURAL RESOURCES (%)
	MINIMUM	ACHIEVED	MINIMUM	ACHIEVED	HATOTIAL RESOURCES (70)
INFRASTRUCTURE	4.5	8.92	900	7422	91%
AIRPORTS	4.5	8.28	900	10444	75%
CITY ROADS	4.5	9.22	900	7987	64%
NATIONAL HIGHWAYS	4.5	7.22	900	8200	84%
STATE HIGHWAYS	4.5	5.88	900	9164	85%
RURAL ROADS	3	5.66	600	6806	90%



CONTACT US







Corporate Office:

Plot No: 403/P, 4th Floor DIVINE BANJARA, ROAD NO. 12, BANJARA HILLS, HYDERABAD - 500034

Website:

www.vishwasamudra.in